# 2014 COSTvsVALUE

www.costvsvalue.com





## **Project Descriptions**

## Midrange

#### ATTIC BEDROOM REMODEL

Convert unfinished attic space to a 15-by-15-foot bedroom and a 5-by-7-foot bathroom with shower. Include a 15-foot shed dormer, four new windows, and closet space under the eaves. Insulate and finish ceiling and walls. Carpet floor. Extend existing HVAC to new space; provide electrical wiring and lighting to code. Retain existing stairs, but add rail and baluster around stairwell.

#### **BACKUP POWER GENERATOR**

Install modular electrical backup system with capacity for providing 70 amps of emergency power in two 240-volt circuits and six 120-volt circuits. Assume existing propane gas supply. Include generator mounted on 2-by-4-four-foot concrete or composite pad, automatic transfer switch, load center, exterior disconnect, and grounding rod. Include 30 feet of conduit and electrical cable for generator connections; grounded cable for circuits; 5 feet of flexible fuel line for connection to existing rigid gas supply line; and automotive-type storage battery.

#### **BASEMENT REMODEL**

Finish the lower level of a house to create a 20-by-30-foot entertaining area with wet bar and a 5-by-8-foot full bathroom; construct 24 linear feet of finished partition to enclose mechanical area. Walls and ceilings are painted drywall throughout; exterior walls are insulated; painted trim throughout. Include five six-panel factory-painted hardboard doors with passage locksets. Electrical wiring to code.

*Main room:* Include 15 recessed ceiling light fixtures and three surface-mounted light fixtures, and a snap-together laminate flooring system.

Bathroom: Include standard white toilet, vanity with cultured marble top, resilient vinyl flooring, two-piece fiberglass shower unit, a light/fan combination, vanity light fixture, recessed medicine cabinet, towel and

paper-holder hardware.

*Bar area:* Include 10 linear feet of raised-panel oak cabinets with laminate countertops, stainless steel bar sink, single-lever bar faucet, undercounter refrigerator, and vinyl floor tile.

#### **BATHROOM ADDITION**

Add a full 6-by-8-foot bathroom over a crawlspace with poured concrete walls. Include cultured-marble vanity top with molded sink; standard chrome faucets; 30-by-60-inch white fiberglass tub/shower with ceramic tile surround; single-lever temperature and pressure-balanced faucet; white low-profile toilet; general and spot lighting; electrical wiring to code; mirrored medicine cabinet; linen storage closet or cabinet; vinyl wallpaper; painted trim; and ceramic tile floor.

#### **BATHROOM REMODEL**

Update an existing 5-by-7-foot bathroom. Replace all fixtures to include 30-by-60-inch porcelain-on-steel tub with 4-by-4-inch ceramic tile surround; new single-lever temperature and pressure-balanced shower control; standard white toilet; solid-surface vanity counter with integral sink; recessed medicine cabinet with light; ceramic tile floor; vinyl wallpaper.

#### **DECK ADDITION (WOOD)**

Add a 16-by-20-foot deck using pressure-treated joists supported by 4x4 posts anchored to concrete piers. Install pressure-treated deck boards in a simple linear pattern. Include a built-in bench and planter of the same decking material. Include stairs, assuming three steps to grade. Provide a complete railing system using pressure-treated wood posts, railings, and balusters.

#### **DECK ADDITION (COMPOSITE)**

Add a 16-by-20-foot deck using pressuretreated joists supported by 4x4 posts anchored to concrete piers. Install composite deck material in a simple linear pattern. Include a built-in bench and planter of the same decking material. Include stairs, assuming three steps to grade. Provide a complete railing using a matching system made of the same composite as the decking material.

## ENTRY DOOR REPLACEMENT (STEEL)

Remove existing 3-0/6-8 entry door and jambs and replace with new 20-gauge steel unit, including clear dual-pane half-glass panel, jambs, and aluminum threshold with composite stop. Door is factory finished with same color both sides. Exterior brick-mold and 2.5-inch interior colonial or ranch casings in poplar or equal prefinished to match door color. Replace existing lockset with new bored-lock in brass or antique-brass finish.

## ENTRY DOOR REPLACEMENT (FIBERGLASS)

Remove existing 3-0/6-8 entry door and jambs and replace with new fiberglass unit with simulated wood grain, stained same color both sides; dual-pane, decorative half-glass panel with zinc caming; PVC-wrapped exterior trim in color to match existing trim; 2.5-inch interior colonial or ranch casings in hardwood stained to match door. Replace existing lockset with mortise lock with lever handle and integrated deadbolt in oil-rubbed bronze or satin-nickel finish.

#### **FAMILY ROOM ADDITION**

In a style appropriate to the existing house, add a 16-by-25-foot room on a crawlspace foundation with vinyl siding and fiberglass shingle roof. Include drywall interior with fiberglass insulation, pre-finished hardwood floor, and 180 square feet of glazing including windows, atrium-style exterior doors, and two operable skylights. Tie into existing HVAC. Add electrical system to code, including 12 recessed ceiling lights.

#### **GARAGE ADDITION**

Construct a 26-by-26-foot freestanding two-car garage, including footings and slab-on-grade foundation, 2x4 wood frame with



#### Project Descriptions continued

OSB structural sheathing, and gable truss roof at 6/12 pitch. Install 25-year asphalt shingle roofing with galvanized metal flashing; vinyl siding and trim. Install five double-hung 30-by-48-inch vinyl windows; one 3-0/6-8 exterior door with half-glass and lockset; and two composite 9-by-8-foot overhead doors with motorized openers. Include 100-amp breaker at main house panel and 50 linear feet of trench buried conduit to feed new electrical subpanel. Provide electrical wiring for openers; three-way switching for fluorescent ceiling fixtures over each bay; three-way switching for two exterior spotlights; outlets to code. Interior wall, floors, and ceilings remain unfinished.

#### **GARAGE DOOR REPLACEMENT**

Remove and dispose of existing 16-by-7-foot garage door and tracks. Install new 4-section garage door on new galvanized steel tracks; reuse existing motorized opener. New door is uninsulated, single-layer, embossed steel with two coats of baked-on paint, galvanized steel hinges, and nylon rollers; 10-year limited warranty.

#### **HOME OFFICE REMODEL**

Convert an existing 12-by-12-foot room to a home office. Install custom cabinets to include 20 linear feet of laminate desktop, computer workstation, and wall cabinet storage. Rewire room for computer, fax machine, and other electronic equipment, as well as cable and telephone lines. Include drywall interior, painted trim, and commercial-grade carpeting.

#### **MAJOR KITCHEN REMODEL**

Update an outmoded 200-square-foot kitchen with a functional layout of 30 linear feet of semi-custom wood cabinets, including a 3-by-5-foot island; laminate countertops; and standard double-tub stainless-steel sink with standard single-lever faucet. Include energy-efficient wall oven, cooktop, ventilation system, built-in microwave, dishwasher, garbage disposal, and custom lighting. Add new resilient flooring. Finish with painted walls, trim, and ceiling.

#### **MASTER SUITE ADDITION**

Add a 24-by-16-foot master bedroom suite over a crawlspace. Include walk-in closet/dressing area, whirlpool tub in ceramic tile platform, separate 3-by-4-foot ceramic tile shower, and double-bowl vanity with solid-surface countertop. Bedroom floor is carpet; bathroom floor is ceramic tile. Painted walls, ceiling, and trim. General and spot lighting, exhaust fan; electrical wiring to code.

#### **MINOR KITCHEN REMODEL**

In a functional but dated 200-square-foot kitchen with 30 linear feet of cabinetry and countertops, leave cabinet boxes in place but replace fronts with new raised-panel wood doors and drawers, including new hardware. Replace wall oven and cooktop with new energy-efficient models. Replace laminate countertops; install midpriced sink and faucet. Repaint trim, add wall covering, and remove and replace resilient flooring.

#### **ROOFING REPLACEMENT**

Remove existing roofing to bare wood sheathing and dispose of properly. Install 30 squares of 235-pound fiberglass asphalt shingles (min. 25-year warranty) with new felt underlayment, galvanized drip edge, and mill-finish aluminum flashing. Assume a 5-square hip roof; custom flashing at two average-size skylights; and custom cap treatment at vented ridge.

#### SIDING REPLACEMENT

Replace 1,250 square feet of existing siding with new vinyl siding, including all trim.

#### **SUNROOM ADDITION**

Construct a 200-square-foot sunroom addition, including footings and slab-ongrade foundation. Post-and-beam framing exposed on interior side. Wall glazing: vinyl or aluminum clad awning and casement windows with low-E, laminated or tempered glazing and screens. Roof glazing: 10 large aluminum-clad venting skylights with screens. Provide ceiling fan; insulate all nonglass areas; provide movable shades for glass area. Quarry tile or equal on floor.

#### **TWO-STORY ADDITION**

Add a first-floor family room and a secondfloor bedroom with full bathroom in a 24-by-16-foot two-story wing over a crawlspace. Add new HVAC system to handle addition; electrical wiring to code.

Family room: Include a prefabricated gas fireplace; 11 3-by-5-foot double-hung insulated clad-wood windows; an atrium-style exterior door; carpeted floors; painted drywall on walls and ceiling; and painted trim.

Bathroom: 5 by 8 feet. Include a one-piece fiberglass tub/shower unit; standard white toilet; wood vanity with solid-surface countertop; resilient vinyl flooring; and mirrored medicine cabinet with built-in light strip; papered walls; and painted trim; exhaust fan. Bedroom: Include walk-in closet/dressing area; carpet; painted walls, ceiling, and trim; general and spot lighting.

#### WINDOW REPLACEMENT (VINYL)

Replace 10 existing 3-by-5-foot double-hung windows with insulated vinyl replacement windows. Wrap existing exterior trim as required to match. Do not disturb existing interior trim.

#### WINDOW REPLACEMENT (WOOD)

Replace 10 existing 3-by-5-foot double-hung windows with insulated wood replacement windows, exterior clad in vinyl or aluminum. Wrap existing exterior trim as required to match. Do not disturb existing interior trim.

## Upscale

#### **BATHROOM ADDITION**

Add a new 100-square-foot master bathroom to existing master bedroom over a crawlspace. Include 42-by-42-inch neo-angle shower with ceramic tile walls with accent strip, recessed shower caddy, body-spray fixtures, and frameless glass enclosure. Include a customized whirlpool tub; stone countertop with two sinks; two mirrored medicine cabinets with lighting; a compartmentalized commode area with one-piece toilet; and a humidistat-controlled exhaust fan. Use all color fixtures. Use larger matching ceramic tiles on the floor, laid on the diagonal with ceramic tile base molding.



#### Project Descriptions continued

Add general and spot lighting including waterproof shower fixture. Cabinetry shall include a custom drawer base and wall cabinets for a built-in look. Extend HVAC system, and include electric in-floor heating and heated towel bars.

#### **BATHROOM REMODEL**

Expand an existing 35-square-foot bathroom to 100 square feet within existing house footprint. Relocate all fixtures. Include 42-by-42-inch neo-angle shower with ceramic tile walls with accent strip, recessed shower caddy, body-spray fixtures, and frameless glass enclosure. Include a customized whirlpool tub; stone countertop with two sinks; two mirrored medicine cabinets with lighting; a compartmentalized commode area with one-piece toilet; and a humidistatcontrolled exhaust fan. Use all color fixtures. Use larger matching ceramic tiles on the floor, laid on the diagonal with ceramic tile base molding. Add general and spot lighting including waterproof shower fixture. Cabinetry shall include a custom drawer base and wall cabinets for a built-in look. Extend HVAC system, and include electric in-floor heating and heated towel bars.

#### **DECK ADDITION (COMPOSITE)**

Add a 16-by-20-foot deck using pressuretreated joists supported by 4x4 posts anchored to concrete piers. At one corner, add a second, 10-foot-diameter six-sided platform one step down from the main deck. Include stairs on the smaller deck, assuming three steps to grade. Install composite deck material in a simple linear pattern. Trim the perimeter joists and wrap the 4x4 posts with composite materials to match the decking. Using the same decking material, include a built-in bench and planter along one 16-foot side. On the remaining perimeter, provide a railing system using composite material of contrasting or complementary colors that includes decorative balusters, post caps, and lighting. Railing and trim should provide for overall curb appeal to the outdoor living space by integrating the deck with the home's color and architecture, creating a custom look.

#### **GARAGE ADDITION**

For the same midrange two-car garage, add interior wall finish using moisture-resistant drywall on ceiling and three walls. At rear wall, install modular storage systems including wall panels, upper and lower storage cabinets with work surfaces, and required task lighting. Trim all windows and doors and provide base molding at perimeter; paint all trim, ceiling, and walls. Finish cement floor with color, slip-resistant epoxy sealer.

#### **GARAGE DOOR REPLACEMENT**

Remove and dispose of existing 16x7-foot garage door and tracks. Install new 4-section garage door on new heavy-duty galvanized steel tracks; reuse existing motorized opener. New door is high tensile strength steel with two coats of factory-applied paint and foam insulated to minimum R-12 with thermal seals between pinch-resistant panels. Windows in top panel are ½-inch insulated glass. Hardware includes galvanized steel hinges and ball-bearing urethane rollers. Lifetime warranty.

#### **GRAND ENTRANCE (FIBERGLASS)**

Remove existing 3-0/6-8 entry door and cut and reframe opening for a 12-36-12 entrance door with dual sidelites. Move double-gang electrical box with two switches. Fiberglass door blank matches upscale entry, including color, threshold, lockset, and decorative halfglass; sidelites match door. PVC-wrapped exterior trim in color to match existing trim; wider interior colonial or ranch casings (3.5-inch to cover new jack studs) in hardwood stained to match door. All work to be completed in one day.

#### **MAJOR KITCHEN REMODEL**

Update outmoded 200-square-foot kitchen with 30 linear feet of top-of-the-line custom cherry cabinets with built-in sliding shelves and other interior accessories. Include stone countertops with imported ceramic- or glasstile backsplash; built-in refrigerator, cooktop, and 36-inch commercial grade range and vent hood; built-in warming drawer, trash compactor, and built-in combination microwave and convection oven. Install high-end undermount sink with designer

faucets and built-in water filtration system. Add new general and task lighting including low-voltage undercabinet lights. Install cork flooring, cherry trim.

#### **MASTER SUITE ADDITION**

Add a 32-by-20-foot master bedroom suite over a crawlspace.

Bedroom: Add a spacious sleeping area with lounging/sitting area adjacent to large master bathroom. Include custom bookcases and built-in storage with millwork details; high-end gas fireplace with stone hearth and custom mantle; and large walk-in closet/ dressing area with natural light, mirrors, and linen storage. Add French doors to exterior. Bathroom: Include a large walk-in shower with dual-shower system, stone shower walls and floor, and custom frameless glass enclosure. Add corner-design whirlpool tub bordered on two sides by windows and built into granite or marble platform with custom cabinet front. Include two sinks in separate custom vanities with stone countertops and large mirrors. Create partitioned area for luxury one-piece toilet.

General: Add 5-foot-long hospitality center with bar sink, undercounter refrigerator, custom cabinetry, granite or marble countertop, and microwave. Include soundproofing, in-floor heating, custom wall finishes and hardware, general and spot lighting, and lighting controls.

#### **ROOFING REPLACEMENT**

Remove existing roofing to bare wood sheathing and dispose of properly. Install 30 squares of standing-seam metal, formed on site into 16-inch panels using factory-enameled roll steel; double-lock all seams. Use custom brake-bent flashing from same material for drip edge and all flashing at roof-wall intersections. Assume a 5-square hip roof; custom flashing at two average-sized skylights; and custom cap treatment at vented ridge. Apply over new felt underlayment; use ice-and-water membrane at eaves, valleys, and all penetrations.



#### Project Descriptions continued

## SIDING REPLACEMENT (FIBER-CEMENT)

Replace 1,250 square feet of existing siding with new fiber-cement siding, factory primed and factory painted. Include all 4/4 and 5/4 trim using either fiber-cement boards or cellular PVC.

## SIDING REPLACEMENT (FOAM-BACKED VINYL)

Replace 1,250 square feet of existing

siding with new foam-backed vinyl siding, including factory trim at all openings and corners.

#### WINDOW REPLACEMENT (VINYL)

Replace 10 existing 3-by-5-foot double-hung windows with insulated, low-E, simulated-divided-lite vinyl windows. Simulated woodgrain interior finish; custom-color exterior finish. Trim exterior to match existing; do not disturb existing interior trim.

#### **WINDOW REPLACEMENT (WOOD)**

Replace 10 existing 3-by-5-foot double-hung windows with insulated, low-E, simulated-divided-lite wood windows. Interior finish of stained hardwood; exterior finish of custom-color aluminum cladding. Trim exterior to match existing; do not disturb existing interior trim.

## **Reuse and Licensing of Data**

#### **COPYRIGHTED MATERIAL**

The Remodeling Cost vs. Value Report contains copyrighted material that is being made available in free downloadable PDF documents as a public service. Any reuse without express permission is prohibited, including but not limited to the following:

- 1. RESALE. The Cost vs. Value Report, whether in whole or part, may not be reproduced and sold in any format, including print, digital, electronic file, fax, or other medium.
- 2. PUBLICATION OF DATA. The Cost vs. Value Report, whether in whole or part, may not be distributed or published in any format, including print, digital, electronic file, fax, or other medium without obtaining express permission.
- 3. APPLICATIONS/SOFTWARE. The Cost vs. Value Report, whether in whole or part, may not be incorporated for use in any kind of computer- or Web-based application, calculator, database, or other automated, electronic, or digital device, instrument, or software except as licensed by Hanley Wood (see Licensing, below).

#### **EXCERPTING COST VS. VALUE REPORT DATA**

Excerpts of Cost vs. Value Report data may not take the form of a chart or table that simulates the manner in which the data is displayed at www.costvsvalue.com.

Excerpts of Cost vs. Value Report data may, however, be made as part of a narrative, provided that the sum total of all excerpts from any publisher in all formats does not exceed data from more than five projects.

#### **ACKNOWLEDGING COST VS. VALUE AS DATA SOURCE**

When excerpting Cost vs. Value Report data, refer to the "Remodeling 2014 Cost vs. Value Report" and include the URL www. costvsvalue.com, as in the following examples:

- "... according to the Remodeling 2014 Cost vs. Value Report (www.costvsvalue.com) ..."
- "... as compiled in the Remodeling 2014 Cost vs. Value Report (www.costvsvalue.com) ...."

This form of citation should be used in the first instance on every page of a multipage online story that cites the Cost vs. Value Report on multiple pages. Subsequent references on a given page may be foreshortened to "Cost vs. Value Report."

All excerpts must be accompanied by one or more instances of the following acknowledgements of copyright:

"© 2014 Hanley Wood, LLC. Complete data from the Remodeling 2014 Cost vs. Value Report can be downloaded free at www. costvsvalue.com."

#### **LICENSING OF 2014 COST VS. VALUE REPORT DATA**

For permission to license data from the 2014 Cost vs. Value Report for use in any kind of computer- or Web-based application, calculator, database, or other automated, electronic, or digital device, instrument, or software, include the following in an email request to costvsvaluepermissions@hanleywood.com

- a description of the application, calculator, or device for which use of the data is being requested. Include the length of time for which the license is sought.
- a detailed description of the material to be licensed (e.g., specific projects, cities, etc.).

## San Antonio, TX

This document contains copyrighted material and is not authorized for display on the Internet or for republication in any media for resale.



PROJECT TYPE	SAN ANTONIO			WES	WEST SOUTH CENTRAL			2014 NATIONAL AVERAGES		
MIDRANGE	Job Cost	Resale Value	Cost Recouped	Job Cost	Resale Value	Cost Recouped	Job Cost	Resale Value	Cost Recouped	
Attic Bedroom Remodel	\$44,519	\$31,348	70.4%	\$44,581	\$36,883	83.0%	\$49,438	\$41,656	84.3%	
Backup Power Generator	11,042	5,750	52.1%	11,116	9,533	86.0%	11,742	7,922	67.5%	
Basement Remodel	55,302	42,565	77.0%	56,110	51,586	92.0%	62,834	48,777	77.6%	
Bathroom Addition	34,354	21,729	63.3%	34,835	23,281	67.0%	38,186	22,940	60.1%	
Bathroom Remodel	14,298	9,565	66.9%	14,546	12,338	85.0%	16,128	11,688	72.5%	
Deck Addition (wood)	8,431	7,175	85.1%	8,534	7,621	89.0%	9,539	8,334	87.4%	
Deck Addition (composite)	14,599	10,850	74.3%	14,698	11,419	78.0%	15,437	11,476	74.3%	
Entry Door Replacement (steel)	1,090	778	71.4%	1,100	1,112	101.0%	1,162	1,122	96.6%	
Entry Door Replacement (fiberglass)	2,743	1,645	60.0%	2,754	1,976	72.0%	2,822	1,997	70.8%	
Family Room Addition	71,813	49,600	69.1%	72,903	53,343	73.0%	80,765	55,540	68.8%	
Garage Addition	46,548	33,283	71.5%	46,542	36,184	78.0%	49,911	34,598	69.3%	
Garage Door Replacement	1,456	832	57.0%	1,425	1,076	76.0%	1,534	1,283	83.7%	
Home Office Remodel	25,406	14,550	57.3%	25,738	14,969	58.0%	28,000	13,697	48.9%	
Major Kitchen Remodel	50,353	37,775	75.0%	50,991	42,797	84.0%	54,909	40,732	74.2%	
Master Suite Addition	93,540	66,430	71.0%	94,383	67,596	72.0%	103,844	70,121	67.5%	
Minor Kitchen Remodel	17,204	13,513	78.5%	17,438	16,533	95.0%	18,856	15,585	82.7%	
Roofing Replacement	15,804	8,976	56.8%	16,229	11,612	72.0%	18,913	12,777	67.6%	
Siding Replacement (vinyl)	10,308	6,622	64.2%	10,387	8,234	79.0%	11,475	8,975	78.2%	
Sunroom Addition	68,088	33,816	49.7%	68,811	39,648	58.0%	73,546	38,011	51.7%	
Two-Story Addition	144,227	101,674	70.5%	145,496	107,034	74.0%	155,365	111,579	71.8%	
Window Replacement (vinyl)	9,252	6,508	70.3%	9,348	7,213	77.0%	9,978	7,857	78.7%	
Window Replacement (wood)	10,105	7,569	74.9%	10,230	7,722	75.0%	10,926	8,662	79.3%	
UPSCALE	Job Cost	Resale Value	Cost Recouped	Job Cost	Resale Value	Cost Recouped	Job Cost	Resale Value	Cost Recouped	
Bathroom Addition	\$66,954	\$41,917	62.6%	\$67,635	\$45,742	68.0%	\$72,538	\$43,936	60.6%	
Bathroom Remodel	48,256	32,012	66.3%	48,627	35,430	73.0%	51,374	32,660	63.6%	
Deck Addition (composite)	32,376	20,600	63.6%	32,675	22,332	68.0%	35,158	22,881	65.1%	
Garage Addition	76,146	44,900	59.0%	77,036	50,222	65.0%	82,311	48,065	58.4%	
Garage Door Replacement	2,674	2,924	109.3%	2,652	2,204	83.0%	2,791	2,315	82.9%	
Grand Entrance	7,098	4,658	65.6%	7,128	5,322	75.0%	7,305	5,163	70.7%	
Major Kitchen Remodel	104,764	65,235	62.0%	104,706	73,054	70.0%	109,935	69,973	63.6%	
Master Suite Addition	209,539	122,010	58.0%	211,488	132,573	63.0%	224,989	125,920	56.0%	
Roofing Replacement	28,185	17,342	61.5%	28,948	20,128	70.0%	34,495	21,731	63.0%	
Siding Replacement (fiber-cement)	12,158	9,618	79.1%	12,067	10,662	88.0%	13,378	11,645	87.0%	
Siding Replacement (foam-backed vinyl)	12,942	8,194	63.3%	12,981	10,260	79.0%	14,236	11,124	78.1%	
Window Replacement (vinyl)	12,846	8,829	68.7%	12,918	9,822	76.0%	13,385	10,252	76.6%	
Window Replacement (wood)	16,103	11,000	68.3%	16,196	12,429	77.0%	16,798	12,438	74.0%	

.014 Hanley Wood, LLC. Republication or dissemination of Remodeling's 2014 Cost vs. Value R. permission of Hanley Wood, LLC. "Cost vs. Value" is a registered trademark of Hanley Wood, I.

CONFIDENCE LEVEL: 95% +/-6.12 CONFIDENCE LEVEL: 95% +/-1.96%

## 2014 COSTvsVALUE



The 2014 Remodeling Cost vs. Value Report has been brought to you thanks to the following companies.













## CONTROL YOUR POWER. YOUR LIFE."



BACKUP POWER IS THE FASTEST GROWING CATEGORY IN YEAR-OVER-YEAR RETURN ON INVESTMENT WITH A 15% JUMP IN 2014 AFTER SEEING A 5% JUMP IN 2013

- Remodeling Magazine 2014

### WHY OFFER THE #1 SELLING RESIDENTIAL BACKUP GENERATOR?

Because the added value of knowing power won't be lost in an emergency helps make your customers feel safe in their homes from the minute you give them the key. Increase your profits and set yourself apart from the competition by joining Generac's Builder Alliance program to enjoy preferred pricing and a network backed by extensive marketing support from a recognized brand.





# DURABLE PRODUCTS. BEAUTIFUL COLORS. COMPLETE SOLUTION.

When you sell James Hardie® products, you're delivering what homeowners want – a beautiful, low maintenance home without sacrifice. James Hardie® siding with ColorPlus® Technology offers your customers superior protection and the #1 return on investment. Come grow your business with America's largest siding manufacturer.

Grow your business at VisualizeJH.com



## Yes, we care...









### ...about adding value and beauty to your home.

The ProVia name represents the company's focus on professional-class products, and reinforces its commitment to delivering unmatched levels of quality and customer satisfaction. Our exterior product portfolio includes brands like Signet Fiberglass Doors, Legacy Steel Doors, Prestige Patio Doors, Aeris Windows, Heartland Siding and Heritage Stone. Our goal is to serve you, by caring for details in ways others won't. We're building our products and our company to last a lifetime. That's The Professional Way.

Visit www.proviaproducts.com to find out how you can experience The Professional Way.



THIS IS MORE THAN A BATH/SHOWER. THIS IS THE DRIVING FORCE BEHIND BATHROOM CONSTRUCTION PROJECTS.


IT IS MANUFACTURED OF SOLID VIKRELL, MATERIAL, WHICH MEANS IT'S AS TOUGH AS NAILS BUT HAT SNAP QUICK, CAULK-FREE INSTALLATION. THIS IS THE ENSEMBLE MEDLEY, BATH/SHOWER. LET'S GET TO WORK.




Learn how beauty meets brawn at SterlingPlumbing.com.









www.thermatru.com



©2014 Therma-Tru Corp. All rights reserved. JAN 2014



Go to waypointlivingspaces.com to learn more.



Exactly what you had in mind®